

Silverline House — 25-Storey Residential HRB

# Construction Control Plan

Document Reference: 1.1

Revision: Rev A

Date: March 2026

Project Reference: SLH-2026

## **1 Introduction**

### ***1 Purpose***

This Construction Control Plan sets out the arrangements for managing building control compliance during construction in accordance with the Building Safety Act 2022 and the Higher-Risk Buildings (Management of Safety Risks etc) (England) Regulations 2023.

### ***2 Inspection Hold Points***

Mandatory inspection hold points are established at: pile installation commencement, transfer slab pre-pour, structural topping-out, facade bracket installation commencement, and practical completion. The BSR will be notified at least 5 working days prior to each hold point.